

SECTION 9: BOILER STARTUP/SHUTDOWN SEQUENCE SOP

Purpose: Standardize boiler startup and shutdown to minimize risks during transitions, ensure component integrity, and meet safety regulations.

Startup Procedures:

Perform a pre-start inspection of all gauges, valves, and interlocks.
Ensure water level is within normal range and feed systems are functional.

Verify fuel supply, purge line traps, and open manual valves.
Begin forced draft blower and initiate purge cycle (per code duration).

Engage ignition system and monitor flame establishment.

Gradually ramp up firing rate and monitor for abnormal pressure/temp.

Check safety interlocks, alarms, and auto-stop mechanisms.

Record operating data every 15 minutes for the first hour.

Shutdown Procedures:

Slowly reduce firing rate and stop fuel input.

Allow fan to run post-purge cycle.

Close manual gas valves and isolate boiler if required.

Record final water level, pressure, and temperature.

Lockout/tagout for maintenance or extended shutdowns.

Notes:

Never skip purge steps.

Log any abnormalities or deviations during transition.