

NEXUM SUUM INCORPORATED

24-Hour Chiller System SOP

These SOPs apply to continuous chiller operations for major manufacturers such as Carrier, Trane, York, and Daikin. Tasks are divided by shift and align with safety, energy efficiency, and performance standards.

Afternoon Shift (2 PM – 10 PM)

- Confirm suction/discharge pressure match panel readings
- Clean condenser coil intake screens (if accessible)
- Record chilled water supply & return temps
- Check sensor and transducer status on BAS or locally
- Inspect condenser pump and tower pump VFDs
- Monitor approach temperature and delta-T

Night Shift (10 PM – 6 AM)

- Cycle tower fans and check speed modulation response
- Ensure tower water temp is within 5°F of design
- Inspect compressor amps and oil pressure (scroll or screw)
- Review alarm history and trip logs
- Ensure system redundancy and cooling capacity is staged
- Perform infrared scan on motor and electrical terminals

Checklist

	Yes / No
Log suction/discharge pressure, Leaving Water Temp	Yes / No
Visually inspect condenser fan operation and speed Record	Yes / No
Chiller kW per ton if sensor enabled	Yes / No
Verify compressor oil level and pressure	Yes / No
Ensure tower fans are cycling and tower basin is clean	Yes / No
Check BAS or local alarm status/history	Yes / No
Log condenser approach temperature (within spec?)	Yes / No