

 2. Test Points & Reference Ranges

Test Point	Method	Ideal Value or Range
Suction Pressure	Gauge at evaporator outlet	55–65 psi (R134a reference)
Discharge Pressure	Gauge after compressor	180–250 psi
ΔT (Chilled Water)	Temp in/out sensors	10°F to 12°F
Condenser Water Flow	GPM meter or differential pressure	Per design spec
Superheat / Subcooling	Refrigerant line clamps	8–12°F / 10–15°F

 3. Emergency Conditions

Event	Required Response
Chiller Trips on High Pressure	Shut system, check condenser water loop
Oil Level Alarm / Seal Failure	Shut down, inspect oil separator
Freeze Alarm on Evaporator	Verify flow & temperature sensors
Compressor Overload or Lockout	Wait 15 min reset; inspect amp draw