

2. Key Test Points

Parameter	Tool/Method	Ideal Range/Result
Pressure on Main Riser	Pressure gauge	120–175 psi (wet system typical)
Flow Switch Delay	Stopwatch	≤ 90 seconds
Tamper Switch Status	Visual panel check	Normal/Ready
Fire Pump Test Log	Manual/auto test	Weekly or per code
Alarm Signal Transmission	Monitoring center check	Successful within 60 seconds

3. Emergency Conditions

Event	Immediate Action
Sprinkler activation	Isolate zone, activate drain
Suppression system discharge	Evacuate area, ventilate, notify EHS
Power loss to suppression panel	Engage backup battery, contact service